



SIDE VIEW

END VIEW

TANK: CATEGORY 4, 4" 750 GALLON 1 COMPARTMENT TANK REINFORCED WITH GRADE 60 #3 REBAR 12" O/C, BOTH WAYS, 4" WALLS AND 4" BOTTOM INLET AND OUTLET RESILIENT CONNECTORS PER ASTM-923-98 CONNECTORS MUST BE USED WITH APPROVED CLAMP CONNECTOR WILL ACCEPT 4" PVC PIPE.

LIDS: 4" LID WITH 1-22" ROUND MANHOLE COVER AT EACH END OF TANK
 8" LID WITH 1-22" ROUND MANHOLE COVER AT EACH END OF TANK
 LID IS REINFORCED WITH GRADE 60 REBAR.

TANK & LIDS: 4000 PSI CONCRETE AT 28 DAYS

IMPRINTED ON INLET END OF TANK:
 LEGEND: PSI 750 STATE APPROVAL NUMBER: 01-011-02S-C4

WEIGHTS: TANK ONLY 6,820
 TANK & 4" LID 8,360
 TANK & 8" LID 9,900

THIS TANK IS RATED FOR H-20 LOADING WHEN USED WITH 8" TRAFFIC LID AND TANK BURIAL DEPTH IS AT LEAST 18" BELOW GROUND SURFACE

THIS TANK COMPLIES WITH SECTION 1003.5.1 OF THE 2001 FLORIDA PLUMBING CODE

INTERCEPTOR CAPACITY PER SECTION 1003.5.1 IS SITE SPECIFIC.

THIS SEWAGE TREATMENT RECEPACLE HAS BEEN DESIGNED, CONSTRUCTED AND STRUCTURALLY TESTED IN ACCORDANCE WITH CHAPTER 64E-6.013, FLORIDA ADMINISTRATIVE CODE, (FAC) DATED MARCH 22, 2000

DRAWING NOT TO SCALE

FLORIDA SEPTIC, INC

P.O. BOX 545
 HAWTHORNE, FLORIDA 32640
 (800) 940-8265

MODEL:		4" 750 GAL. TANK
REVISED:	APPROVAL DATE:	
05/01/2011	05/31/2001	